



Scobbo Foundation Systems Installs (110) Helical Piles for Sag Harbor Historical Library Restoration and Expansion



Scobbo Foundation Systems
Division of Frank Scobbo Contractors, Inc.
Long Island, NY Piscataway, NJ
(516) 944-7154 (516) 944-PIER
www.nynjhelix.com



Project Name & Location:	John Jermain Memorial Library, Sag Harbor, New York
Project Date:	2013-14
Project Type:	Underpinning and Shoring of Existing Concrete Piers and Footings Foundation and Deep Foundations for 5000 sq. ft. Building Expansion
Helical Pile Installation Contractor:	Frank Scobbo Contractors , Long Island & Piscataway
General Contractor:	Trunzo Building Corp - East Hampton, New York
Engineering Company:	Newport Engineering - Oyster Bay, New York
Helical Piles Specifications:	(50) 3.5" Diameter Piles with 12" 14" .5" thick; Helix Bearing Plates; (60) 5.5" Diameter Piles with 14" 16" .75" thick Helix Bearing Plates; All Piles were Installed to Minimum 30 Ton Compression Load with Torque Ranging from 12,000 to 80,000 ft. lbs.; All Piles were Galvanized
Soils & Embedment Depth:	Sandy Soils with N Values of 50 BPF were Encountered at Approximately 25 ft. Average Embedment Depth was 21-22 ft.
Project Timeline:	First Piles in Dec '13; Final Piles in May '14 with Several Mobilizations
Helical Pile Manufacturer:	IDEAL Group, Webster, NY

Project Overview

The [John Jermain Memorial Library](#) on Main Street in the Village of Sag Harbor is a 4-story structure originally built in 1910. The village decided to do some renovation work and add an additional 5000 sq. ft. of space to the back of this historic structure. The original foundation for this brick and limestone building consists of concrete piers and footings.

After the soils examination [Frank Scobbo](#) worked closely with [Newport Engineering's](#) Chief Engineer, *Nick DeSantis*, on the design and installation plan for both the underpinning piles and the new deep foundation piles. Especially challenging was the installation of the interior piles due to low overhead and tight working quarters. Small installation equipment and 3' and 5' pile sections made the installation a slower and more tedious process. The foundation work was planned to take place in segments, and all of the piles were successfully installed from December '13 to May '14. The project is expected to be completed by the winter of 2014.

Underpinning the Existing Structure

Underpinning the existing structure required that helical piles be installed on both the inside and outside of the existing walls and foundation.

Both 3.5" and 5.5" diameter helical piles were installed for the underpinning, which made the interior installations very challenging due to overhead restrictions combined with the necessity to have higher torque installation equipment inside the structure. 3 ft. and 5 ft. helical pile sections were used for the interior piles.

The helical piles for the underpinning and shoring were installed to a minimum capacity of 30 tons. Each underpinning pile and underpinning bracket were proof tested to 3 tons using calibrated hydraulic jacks. Once all underpinning piles were installed, the piles were loaded to 6 tons and were secured.

Excavating, Retaining Wall Construction and Helical Pile Installation

Scobbo Contractors was contracted to do all of the excavation work, install drilled casings, drive H piles, build the retaining wall and install the helical pile deep foundations.

Both 3.5" and 5.5" diameter helical piles were installed using mostly 20 ft. sections. The 3.5" piles had (2) helix bearing plates - 12" and 14" that were .5" thick. The 5.5" piles also had (2) helical bearing plates - 14" and 16" that were .75" thick. The helical piles were all hot dip galvanized and were manufactured by IDEAL Group.

Both vertical and batter piles were installed. There was (1) successful load test conducted on the 3.5" piles to 30 tons. The 5.5" piles were designed with a safety factor of (3), so no load tests were conducted. 12,000 and 80,000 ft. Lb. Torque motors were used to install the helical piles, and both digital and hydraulic torque indicators were used by the installers and the engineers for torque verification.

The majority of the piles were installed from December through March during the brutal northeast winter. The final piles were installed in early May, and the project is scheduled to be completed this coming winter.

