



Helical Anchors Inc Installer - Pilotes Helicoidales C.R. S.A. - Installs (79) Helical Piles as Deep Foundations for a Reticulated Mezzanine Slab Elevated 3.5 Ft. Above Grade in Tortuguero National Park



Pilotes Helicoidales C.R S.A.
San Jose, San Jose Province
Costa Rica 10103
<https://www.facebook.com/piloteshelicoidalescostarica>

Project Name & Location:	Plazoleta Tortuguero, 4 Esquinas Station, Tortuguero National Park, in Caribbean. Central America
Project Date:	August 2020
Project Type:	Deep Foundations
Helical Pile Installation Contractor:	Pilotes Helicoidales C.R. S.A.
Structural Engineer:	Miguel Cruz y Asociados Ingeniería Estructural LTDA.
General Contractor:	REYCO Recubrimientos y Construcciones S.A.
Helical Piles Specifications:	(31) 3.5" Round Shaft galvanized helical piles, 14ft deep, 25.5 Kip ultimate compression capacity and 20.0 Kip ultimate tension capacity. (48) 3.5" Round Shaft galvanized helical piles, 19ft deep, 49.0 Kip ultimate compression capacity and 41.0 Kip ultimate tension capacity.
Soils & Embedment Depth:	Loose to dense clayey sands with water level at 2.3ft below ground level. Pile cap 3 ft above ground level.
Project Timeline:	(5) Days
Helical Pile Manufacturer:	Helical Anchors Inc. - Minneapolis, MN

Key Benefits:

The galvanized helical pile alternative was cost effective against the original design of driven pipe piles, which would have needed to be treated against corrosion because of being installed near the channels in areas with a high probability of flooding. Another key benefit of the helical piles being the most appropriate solution was the limited access to the site (transportation via barge and challenging navigation through multiple river channels and access through an existing metallic gantry). The superficial soil was so poor in bearing capacity additional metal plates and wood were required for the mobility and positioning of the installation machinery, in this case a back hoe.

